

1 040507

2-8

103

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-20,852-0000  
150' N & 65' E of  
C SW SE, SEC. 13, T 34 S, R 12 W  
810 feet from S section line  
1915 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006

Lease Name Harbaugh Well # 1-13

Operator: Molz Oil Inc.

County Barber

Name & Address Rt 2, Box 54

Well Total Depth 4785 155.51 feet

Kiowa, KS 67070

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 312

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:15 a.m. Day: 8 Month: 2 Year: 19 91

Plugging proposal received from Ron Molz

(company name) Molz Oil Inc. (phone) 316-825-4338

were: 4 1/2" at 4781' w/150 sx cement, PBTD 4746', Perfs at 4692-4721'

1st plug sand back to 4640' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 8 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4640' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement. Maximum pressure 350 psi and shut in 200 psi.

Surface pipe plated with 4 1/2" collar to pump through.

2-13-91  
FEB 13 1991

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3350' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

Reserve this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 2-27-91

INV. NO. 30921