

1 010191

DEC 6 1986

API NUMBER 15- 007-01,016 -0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NW, SEC. 13, T 34 S, R 12 W/EK
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006

Lease Name Harbaugh Well # 2

Operator: Molz Oil Company
Name & Address: R.R. #2, Box 54
Kiowa, KS 67070

County Barber 173.45
Well Total Depth 5337 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 415

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Co. License Number 5418

Address Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 12:40 p.m. Day: 6 Month: 12 Year: 19 86

Plugging proposal received from Vince Schrepel

(company name) Allen Drilling Co. (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1446'

1st plug at Arbuckle with 80 sx cement, 2nd plug at Base Anhydrite with 50 sx cement,
3rd plug at 445' with 30 sx cement, 4th plug at 0-40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 6:30 p.m. Day: 6 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 5280' with 80 sx cement,

2nd plug at 1800' with 50 sx cement,
3rd plug at 445' with 30 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

DEC 9 1986
12-9-86
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

Signed *Jack Luthi* (TECHNICIAN)

DATE 12-10-86

INV. NO. 15579

12-6 JAN 0 8 1987

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

7-1 708

Starting Date December 1, 1986

API Number 15-007-01,016-00-01

OPERATOR: License # 6006
Name Molz Oil Company
Address R.R. #2, Box 54
City/State/Zip Kiowa, Kansas 67070
Contact Person Jim Molz
Phone 316-296-4558

NW NW NW Sec. 13 Twp. 34 S. Rg. 12
4950 Ft. from South Line of Section
4950 Ft. from East Line of Section

CONTRACTOR: License # 5418
Name Allen Drilling Co.
City/State Great Bend, KS.

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330 feet
County Barber

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Cas Inj Pool Ext Air Rotary
X OWWO Expl X Wildcat Cable

Lease Name Harbaugh Well # 2
Ground surface elevation 1446 feet MSL
Domestic well within 330 feet: yes X no

If OWWO: old well info as follows:
Operator Flynn Oil Company
Well Name Humphrey #1
Comp Date 1-28-49 Old Total Depth 5337

Municipal well within one mile: yes X no
Depth to bottom of fresh water 150
Depth to bottom of usable water 200
Surface pipe by Alternate: OWWO 1 X 2
Surface pipe 1.0 3/4 - 415' w/250sx
Conductor pipe required none
Projected Total Depth 5337 feet
Formation Mississippi

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 11-26-86 Signature of Operator or Agent Title President

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 715 feet per Alt.
This Authorization Expires 6-1-87 Approved By 12-1-86

NW. NW. NW Sec. 13 Twp. 34 S. Rg. 12 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 0 - 40' feet depth with 10 sxs of common
2nd plug @ 445' feet depth with 30 sxs of common
3rd plug @ Base anhydrite feet depth with 50 sxs of common
4th plug @ Arbuckle feet depth with 80 sxs of common
5th plug @ feet depth with sxs of
(2) Rathole with 15 sxs (b) Mousehole with sxs

Table with columns: PUSHER, TD, SURFACE PIPE @, ANHYDRITE, ELEVATION, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ FT. W/ SX, 2nd PLUG @ FT. W/ SX, 3rd PLUG @ FT. W/ SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/, MOUSE HOLE CIRCULATED W/, WATER WELL PLUGGED W/, CEMENT COMPANY, TECHNICIAN. Includes date stamp DEC 9 1985 and 5337.