

To: 1 041244 4-23
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 31229
Operator: DLB Oil & Gas, Inc.
Name:
Address 1601 NW Expressway, Ste. 700
Oklahoma City, OK 73118-1401

API NUMBER 15- 007-01,038-00-0)
75' N of
NE NW SW, SEC. 17, T 34 S, R 12 W/4
2385 feet from S section line
990 feet from WK section line
Lease Name DLB Cook Well # A2 (was V.L. Cook #A-1)
County Barber 152.10
Well Total Depth 4680 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address Medicine Lodge, KS

Company to plug at: Hour: 10:15 a.m. Day: 23 Month: 4 Year: 1997

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" at 4680' w/150 sx cement, PBD 4569', Perfs at 4500-05'

1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Mike Maier
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 23 Month: 4 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 4420' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Stephen J. Pender
(TECHNICIAN)

DATE 4-28-97

WV. NO. 48018