

1 010170

15-007-00215-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

NW NE SE, SEC. 17, T 34 S, R 12 W/E

2310 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name V.L. Cook Well # 1 SWD

Operator: Mobil Oil Company

County Barber 155.84

Name & Address Box 5444 Term, Annex

Well Total Depth 4795 feet

Denver, CO 80217

Conductor Pipe: Size _____ feet

Surface Casing: Size 9 5/8 feet 357

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well x D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hayes Well Service License Number 5429

Address Box 108, Attica, KS 67009

Company to plug at: Hour: 10:30 a.m. Day: 16 Month: 9 Year: 19 86

Plugging proposal received from Marvin Capps

(company name) Hayes Well Service (phone) 316-254-7621

were: 5 1/2" at 4795' PBTD 4759' Perfs 4727-4756 Elevation 1490" GL

1st plug sand back to 4500' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx Hulls, 15 sx jel, 50 sx cement, 10 sx jel, release plug, pump 150 sx cement

Plugging Proposal Received by Jack Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:10 a.m. Day: 16 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4648' and dumped 5 sx cement on top of sand through bailer

2nd plug squeezed well with 2 sx hulls, 15 sx jel, 50 sx cement, 10 sx jel, released plug and pumped 150 sx cement

Maximum pressure 450 psi and shut in 250 psi.

Remarks: Recovered 2600' of 5 1/2" casing. Used 60/40 Pozmix 2% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 9-23-86

INV. NO. 15004

9-16

SEP 23 1986
9-23-86

Signed Jack Luthi
(TECHNICIAN)