

To: 040604 ✓  
STATE CORPORATION COMMISSION 15-007-10377-0000  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 8/3/36  
NE SW NW, SEC. 18, T. 34 S, R. 14 W/EX

64  
R

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010  
Operator: Knighton Oil Company, Inc.  
Name & Address: 710 Petroleum Building  
Wichita, KS 67202

3630 feet from S section line  
4290 feet from E section line

Lease Name Davis Well # 2  
County Barber  
Well Total Depth 5236 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 12 1/2" feet 296

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 9:30 a.m. Day: 26 Month: 12 Year: 1991

Plugging proposal received from Mark Morgenstern  
(company name) Clarke Corporation  
were: 7" at 4718', PBTD 4930', Open hole 4718-4930'

RECEIVED  
STATE CORPORATION COMMISSION  
2-6-92  
FER (161992) 316-886-5665  
CONSERVATION DIVISION  
WICHITA, KANSAS

1st plug sand back to 4675' and dump 7 sx cement on top of sand through bailer,

2nd plug run 2 3/8" tubing in to 630', circulate 7" to surface through tubing with 100 sx.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45 a.m. Day: 26 Month: 12 Year: 1991

ACTUAL PLUGGING REPORT 1st plug sanded back to 3470' and dumped 7 sx cement on top of sand bridge through bailer,

2nd plug ran 2 3/8" tubing in to 630'. Circulated 7" to surface through tubing with 103 sx cement. Pulled tubing out of hole, topped out 7" casing with 12 sx cement.

Casing leak had been squeezed at 600' in the past. Cement circulated out 12 1/2" X 7" annulus-dug out cellar to verify cement to surface on backside.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (could) observe this plugging.

DATE 2-17-92  
INV. NO. 34561

Signed Stephen J. Pfeifer  
(TECHNICIAN)