

To: 1 040737
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-9

API NUMBER 15-007-22,317-0000 20R

C NE, SEC. 13, T 34 S, R 14 W 1/4
3960 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Clarke Well # K-1

Operator: Marathon Oil Corp.

County Barber

Name & Address RR 1, Box 25

Well Total Depth 5070 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 407.

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 8:30 a.m. Day: 9 Month: 2 Year: 19 93

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4995' w/150 sx cement, PBDT 4955', Perfs at 4776-4887'

1st plug sand back to 50' above perfs and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

RECEIVED
CORPORATION COMMISSION
2-17-93

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part CONSERVATION DIVISION X WICHITA, KS

Operations Completed: Hour: 9 a.m. Day: 9 Month: 2 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4720' and dumped 2 sx cement on top of plug through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 300 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3414' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I checked (if not) did not observe this plugging.

DATE 2-22-93
CML NO. 3740P

Signed Stephen J. Pfeifer (TECHNICIAN)