

*Corrected

22133-00-00

off 10/30/02

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22589-00-00
Spot: S2NENW Sec/Twnshp/Rge: 13-34S-14W
760 feet from N Section Line, 1880 feet from W Section Line
Lease/Unit Name: BOUZIDEN TRUST Well Number: 2
County: BARBER Total Vertical Depth: 5410 feet

Operator License No.: 5506 Conductor Pipe: Size _____ feet: 8 1/2 83
Op Name: WOOLSEY PETROLEUM CORPORATION Surface Casing: Size 10.75 feet: 259 WITH 220 SX CMT
Address: 125 N. MARKET, SUITE 1000 Production: Size 4.5 feet: 5398 WITH 175 SX CMT
WICHITA, KS 67202 Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2002 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN DICK Company: WOOLSEY PETROLEUM Phone: (316) 267-4379

Proposed Plugging Method: SET 4-1/2" CIBP @ 4100'. PLACE 2 SX ON TOP OF CIBP WITH BAILER. CUT & LAY DOWN CAING THROUGH TBG. SPOT WITH 50 SX @ 600', 75 SX @ 300' AND 25 SX @ 40'. FILL TO SURFACE. SPOT 12 SX GEL AHEAD OF 1ST PLUG AT 600'.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/26/2002 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 5351'. DV TOOL @ 4230' CEMENTED WITH 75 SX CMT. PERFS AT 5216-21, CIBP @ 5170' WITH 25 SX CMT. PERFS AT 4153-59'. SET CIBP @ 4100' & PUT 2 SX CMT ON TOP OF CIBP. LAID DOWN CASING AND RUN 2 3/8" TUBING IN TO PLUG THROUGH. 1ST PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 25 SX CMT.

RECEIVED
SEP 04 2002
9-4-02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3500' OF 4 1/2" CASING.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 9-4-02
INV. NO. 2003060469

Form CR-273