

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,971-0000

LEASE NAME Mills

WELL NUMBER 1-33

SPOT LOCATION SE NW

SEC. 33 TWP. 30 RGE. 14 (X) or (W)

COUNTY Barber

Date Well Completed 12-30-84

Plugging Commenced 12-31-84

Plugging Completed 12-31-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KAN-EX, INC.

ADDRESS 110 S. Main Suite 800 Wichita, KS 67202

PHONE # (316) 267-2585 OPERATORS LICENSE NO. 6327

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Plugged well with 110 sxs 60/40 poz, 2% gel, 3% cc as follows: 800' - 50 sxs; 480' - 40 sxs; 40' - 10 sxs with solid bridge; rathole - 10 sxs. Job by Sun Cementing. Plug down at 9pm on December 31, 1984.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P.O. Box 329 Pratt, Kansas 67124

STATE OF KANSAS COUNTY OF PRATT, ss.


James A. Easter

(employee of operator) or IAN 14 1985

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James A. Easter

(Address) P.O. Box 329 Pratt, Ks. 67124



SUBSCRIBED AND SWORN TO before me this 11 day of January, 1985

Mary L. Tjaden
Notary Public

My Commission expires: 3/22/88



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLERS' WELL LOG


Mills #1-33
 SE NW Sec. 33-30-14W
 Barber County, Kansas
 Commenced : 12-18-84
 Completed : 1-2-85
 API #15-007-21,971
 Operator : Kan-Ex, Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	313	Red Bed	Ran 11 joints (441') new, 24#, 8 5/8" surface pipe.
313	970	Red Bed, Sand	Set at 451' with 275 sxs Class A, 2% gel, 3% cc.
970	1018	Red Bed	Job by Dowell, ticket #03-06-4801. Cement did circulate. Plug down at 1:15pm on December 19, 1984.
1018	1361	Red Bed, Sand	RTD 4750'
1361	1887	Sand, Shale	Plugged well with 110 sxs 60/40 poz, 2% gel, 3% cc as follows: 800' - 50 sxs; 480' - 40 sxs; 40' - 10 sxs with solid bridge; rathole - 10 sxs. Job by Sun Cementing ticket #204579. Plug down at 9pm on December 31, 1984. State Plugger was out of the Dodge City, Kansas office.
1887	2810	Shale	
2810	4750	Lime, Shale, T.D.	

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.



James A. Easter
 James A. Easter, Operations Coordinator

RECEIVED
 STATE COMMISSION
 JAN 14 1985
 1-14-85
 CONSERVATION DIVISION
 Wichita, Kansas

My Commission Expires:
3/22/88

Mary L. Tjaden
 Mary L. Tjaden, Notary Public