

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-20,855-0000
 LEASE NAME Graves A
 WELL NUMBER 2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

990 Ft. from S Section Line
3630 Ft. from E Section Line
 SEC. 33 TWP. 34S RGE. 12 ~~XXXX~~(W)
 COUNTY Barber
 Date Well Completed 12-79
 Plugging Commenced 7-92
 Plugging Completed 7-21-92

LEASE OPERATOR Gore Oil Company
 ADDRESS P.O. Box 2757
 PHONE#(316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)
 Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes
 Which KCC/KDHE Joint Office did you notify? Dodge City
 Is ACO-1 filed? Yes if not, is well log attached? See CP-1

Producing Formation Mississippi Depth to Top 4834' Bottom 4834' T.D. 4900'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	oil/gas	0	324'	8 5/8"	324'	---
		0	4899'	4 1/2"	4899'	3600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plug back with sand to 4780'. Dump 4 sx common. Rip and pull 3600' 4 1/2" casing. Pump down 8 5/8" - 300# hulls, 10 sx gel, 50 sx 60/40, 6% gel, 10 sx gel, 100# hulls, 100 sx 60/40, 6% gel. MTP - 200 psi, ISIP - 100 psi. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105
 Address Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheurman (Employee of Operator) ~~XXXX Operator of~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]
 (Address) P.O. Box 2757, Wichita, KS 67201-2757

SUBSCRIBED AND SWORN TO before me this 31st day of July

[Signature]
 Notary Public

My Commission Expires: 1-7-95

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 3 1992
 8-3-92
 CONSERVATION DIVISION
 Wichita, Kansas
 Revised 08-84



CONTRACTOR'S WELL LOG

JUN 17 1992

OPERATOR: Ram Petroleum Corp.
 CONTRACTOR: Union Drilling Co., Inc.
 LEASE NAME: #2 Graves
 LOCATION: NW SE SW Section 33-34S-12W
 Barber County, Kansas
 COMMENCED: December 17, 1979
 COMPLETED: December 30, 1979

0	1685	Red Bed
1685	3630	Shale
3630	3854	Shale & lime
3854	4575	Lime & shale
4575	4900	Lime
4900		TD

We certify that the above foregoing is a true and correct copy of the log on the #2 Graves, NW SE SW Section 33-34S-12W, Barber County, Kansas.


Union Drilling Co., Inc.

R. D. Messinger
R. D. Messinger

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 31st day of December, 1979.

My appointment expires: 6-2-82



Cynthia L. Romey
Cynthia L. Romey-Notary Public
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
6-18-92
JUN 18 1992
REGISTRATION DIVISION
Wichita, Kansas