

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-20,957-00-01

LEASE NAME Graves A

WELL NUMBER 4 SWD

990 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 33 TWP. 34SRGE. 12 (XXXX(W))

COUNTY Barber

Date Well Completed 8-80

Plugging Commenced 7-92

Plugging Completed 7-21-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gore Oil Company

ADDRESS P.O. Box 2757

PHONE# (316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? See CP-1

Producing Formation n/a Depth to Top n/a Bottom n/a T.O. n/a

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	oil/gas	0	415'	10 3/4"	415'	---
		0	4863'	8 5/8"	4863'	3500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plug back with sand to 4320'. Dump 4 sx common. Rip and pull 3500' 4 1/2". Pump down 10 3/4" - 300# hulls, 10 sx gel, 50 sx 60/40, 6% gel, 10 sx gel, 100# hulls, 150 sx 60/40, 6% gel.
MTP - 200 psi, ISIP - 150 psi. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott W Scheuerman (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) [Signature]

(Address) P.O. Box 2757, Wichita, KS 67201-2757

SUBSCRIBED AND SWORN TO before me this 31st day of July

[Signature]
Notary Public

My Commission Expires: 1-7-95



15-007-20957-00-01

CONTRACTOR'S WELL LOG

AUG 27 1980

OPERATOR:	Ram Petroleum Corp.
CONTRACTOR:	Union Drilling Co., Inc.
LEASE NAME:	#4 Graves
LOCATION:	NW SW SW Section 33-34S-12W Barber County, Kansas
COMMENCED:	July 26, 1980
COMPLETED:	August 4, 1980

0	1290	Redbed & shale	Set 10-3/4" at 415'
1290	4310	Shale	With 300 sacks common, 2% gel.,
4310	4485	Shale & lime	3% Ca. Cl.
4485	4619	Lime & shale	
4619	4719	Shale & lime	
4719	4864	Lime	
4864		TD	

We certify that the above foregoing is a true and correct copy of the log on the # 4 Graves, NW SW SW Section 33-34S-12W, Barber County, Kansas.


Union Drilling Co., Inc.

R. D. Messinger
R. D. Messinger

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the afroesaid County and State as of this 12th day of August, 1980.

My appointment expires: _____



Cynthia L. Romey
Cynthia L. Romey - Notary Public
RECEIVED
STATE OCCUPATION COMMISSION
JUN 18 1982
6-18-82
CONSERVATION DIVISION
Wichita, Kansas