

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-21,147-0000

LEASE NAME VOGEL

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 8  
Ft. from S Section Line

Ft. from E Section Line  
NW SE SE

SEC. 33 TWP. 34S RGE. 12 (E) or (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 1-9-91

Plugging Completed 1-25-91

LEASE OPERATOR J B GAS DETECTORS (ROBERT MCCANDLESS)

ADDRESS 719 Illinois Pratt, Ks. 67124

PHONE# (316) 672-6681 OPERATORS LICENSE NO. 39-6

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Jan. 2, 1991 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ PBTD Bottom 4826 T.D. 4826  
Perfs: 4770-4780.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	318	8 5/8	318	0
		0	4813	4 1/2	4813	3105' 79 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

1-9-91: Found TD at 4690, after dumping sand, dumped 4 sx. cement on top of sand.

1-11-91: Dia Log found free point, shot off at 3105 and pulled 79 jts + cut off jt.

1-25-91: Allied Cement top hole plugged with 300# hulls, 10 sx. gel, 50 cement, 10 gel, 100# hulls, 125 sx. cement, 60-40 poz, 62 gel 700# max. pressure, 300# S I P.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, Inc. License No. 5893

Address P.O. Box 847 Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: J B GAS DETECTORS

STATE OF Kansas COUNTY OF Pratt, ss.


JUDY BERRY

PLUGGING CONTRACTOR  
(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Pratt Well Service, Inc.



SUBSCRIBED AND SWORN TO before me this 3rd day of January, 19 91

My Commission Expires February 6, 1993

Notary Public