

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued November 30, 1967.RECEIVED
STATE CORPORATION COMMISSION
1-15-68
JAN 15 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shenandoah Oil Corporation

Complete Address: 1018 Commerce Bldg., Fort Worth, Texas, 76102

Lease Name Birdie B. Clarke "A" Well No. # 1

Location App. C E/2 Sec. 13 Twp. 34 Rge. 14 (E) (W)W

County Barber Total Depth 4855'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas 67104 License No. 583

Operation Completed: Hour 12:30PM Day 13th Month January Year 1968

The Above well was plugged as follows:

374' of 8 5/8" surface pipe, cemented with 250 sacks. 4854' of 4 1/2" long string
cemented with 100 sacks. Top perferation 4800'. 50 sacks of cement was pumped
on bottom, with the top of the cement at 4626'. 3339' of 4 1/2" long string was
recovered from the hole. Fluid in the hole was bailed down to 300', bridge
plug and rock bridge from 300' to 290', and cmented with 25 sacks, with cement
from 290' to 215'. Hole was filled with mud to 40', rock bridge from 40' to
30', and cemented with 10 sacks, with cement from 30' to the base of the
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving

Well Plugging Supervisor

DATE 1/15/68INV. NO. 7094-W