

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1966

12-23-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Shenandoah Oil Corporation

Complete Address: 406 Mutual Savings Bldg., Fort Worth, Texas

Lease Name Birdie B. Clarke "A" Well No. # 1

Location 150'N of C E/2 Sec. 13 Twp. 34 Rge. 14 (E) (W)W

County Barber Total Depth 4855'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza, Wichita, Kansas License No. _____

Operation Completed: Hour 4:00PM Day 20th Month Dec. Year 1966

The Above well was plugged as follows:

381' of 8 5/8" surface pipe, cement circulated with 250 sacks. Hole
was filled with drilling mud to 350', 1st cementing plug, bridged
with 2 sacks of dry cement and 1/2 sack of hulls on fluid at 350', and
cemented with 23 sacks. Hole was filled with drilling mud to 40', 2nd
cementing plug, bridged with 1 sack of dry cement, and 1/2 sack of hulls
on fluid at 40', and cemented with 9 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/23/66
INV. NO. 4509-w

Signed: Arlene Elving
Well Plugging Supervisor