

K KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1966
1-17-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Alexander Well No. # 1

Location NW NW NW Sec. 3 Twp. 30 Rge. 14 (E) (W) W

County Barber Total Depth 4558'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 10:30AM Day 14th Month Jan. Year 1966

The Above well was plugged as follows:

360' of 8 5/8" surface pipe, cement circulated. 4556' of 5 1/2" long string,
cemented with 100 sacks. Top perferation 4500'. Bottom of the hole was
sanded to 4475', and cemented with 5 sacks, through the dump bailer.
3920' of 5 1/2" long string was recovered from the hole. Fluid in the hole
was at 290', bridge plug and rock bridge from 290' to 280', and cemented
with 25 sacks. Hole was filled with mud to 40', rock bridge from 40' to
30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1/17/66
INV. NO. 2602-U

Signed: Archie Elving
Well Plugging Supervisor