

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 11 1964
5-11-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Graham-Michaelis Drilling Co.

Complete Address: 211 N. Broadway, Wichita, Kansas

Lease Name Farley Well No. # 2

Location NW NW Sec. 29 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4766

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1:30PM Day 8th Month May Year 1964

The Above well was plugged as follows:

749' of 8 5/8" surface pipe, cement circulated. 4760' of 5 1/2" long string,
cemented with 250 sacks. Top perforation 4738'. Bottom of the hole was
sanded to 4725', and cemented with 5 sacks. Hole was bailed down to 250',
Plug was set at 250', with 10' of rock bridge, and cemented with 25 sacks.
Hole was filled with mud to 40', with 10' of rock bridge, and cemented
with 10 sacks to base of the cellar.
3815' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/12/64

INV. NO. 9/21-W

Signed: Archie Elving
Well Plugging Supervisor