

15-007-01695-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1962
12-26-62

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name W.M. Gruenerwald

Complete Address: 35 East Wacker Drive, Chicago, Illinois.

Alexander

Lease Name Alexander #1 Well No. #1

Location NW-NE Sec. 29 Twp. 34S Rge. 14 (E) (W) X

County Barber County Total Depth 4743'

Abandoned Oil Well Abandoned Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Sargants Caseing Pulling Service.

Address: 221 South 9th Street Liberal, Kansas. License No. 511

Operation Completed: Hour 5PM Day 20 Month Dec. Year 1962

The Above well was plugged as follows:

4742' of 5 1/2" oil string. top perforation at 4670'. Hole sanded to 4378'
and 25 sacks cement by Globe Cementing Co. 957' of 8 5/8" surface pipe
circulated with cement. Hole filled to 500' with mud, 10' rock bridge
and 20 sacks cement. Hole filled to 40' with mud, 10' rock bridge and
10 sacks cement to base of cellar. Recovered 3992' of 5 1/2" pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-27-62

INV. NO. 6318-W

Signed: Harmon J. Gustaf
Well Plugging Supervisor