

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 3 TWP. 30 RGE 14 ~~XX~~
Location as in quarters or footage from lines:
660' ESL 1980' FEL

Lease Owner Vincent Oil Corporation
Lease Name Ayres Well No. 1
Office Address 125 N. Market #1110 Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed 9-13-83
Application for plugging filed 9-12-83
Plugging commenced 9-13-83
Plugging completed 9-13-83 @3:00 A.M.
Reason for abandonment of well or producing formation
Dry when drilled

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Richard Lacey, contacted
Producing formation -0- Depth to top bottom T.D. 4670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from feet
to feet for each plug set.

Plugged with 60/40 poz, 2% gel, 3% CC as follows: 50 sxs @780',
40 sxs @450', 10 sxs @40' with solid bridge plug, 10 sxs in mousehole,
10 sxs in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wheatstate Drilling Rotary # 2

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
RICHARD A. HIEBSCH (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Richard A. Hiebsch
1110 KSB Bldg., Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 83.

My Commission expires: June 17, 1985

RECEIVED
Ruth N. Benjamin
Notary Public.



OCT 19 1983
10-19-83
CONSERVATION DIVISION
Wichita, Kansas



- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLERS' WELL LOG

Ayres # 1
 C SW SE Sec. 3-30-14W
 Barber County, Kansas
 Commenced : 9-01-83
 Completed 9-13-83
 API# 15-007-21,660
 Operator : Vincent Oil Corporation

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 19 1983
 9-19-83
 CONSERVATION DIVISION
 Wichita, Kansas

Depth From	To	Formation	Remarks
-0-	10	Clay	Spudded at 12:00 noon on 9-1-83. Drilled 12 1/4" hole to 425', 7 7/8" to 1200'. Set 10 joints (403')
10	100	Sand & Gravel	24#, 8 5/8" new surface casing @418'. Cemented with 250 sxs 50/50 poz, 2% gel, 3% CC. 100 sxs Class H 3% CC. Cement did cir. Plug down @6:15 A.M. on 9-2-83. Buie tkt. # 1493.
100	1200	Red Bed	
1200	1970	Shale	
1970	4670	Lime, Shale T.D.	R.T.D. 4670'. Plugged well with 60/40 poz, 2% gel, 3% CC, 50 sxs @780', 40 sxs @450', 10 sxs @40' with solid bridge plug, 10 sxs in mousehole, 10 sxs in rathole. Job complete @3:00 A.M. 9-13-83. Cement by Buie tkt. # 1500. State plugger contacted, Richard Lacy.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

My Commission Expires:
April 23, 1983

[Signature]
 R. BELDING, VICE-PRESIDENT
[Signature]
 Darlene Butts Notary Public