

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barber County, Sec. 3 Twp. 30 Rge. 14 (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines NW NW NW
Lease Owner H. C. Bennett
Lease Name Alexander Well No. 1
Office Address 1212 Union National Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 1-15-59 19
Application for plugging filed 1-11-66 19
Application for plugging approved 1-13-66 19
Plugging commenced 1-13-66 19
Plugging completed 1-14-66 19
Reason for abandonment of well or producing formation depleted

NORTH

Section Plat grid with 'X' in the top-left cell.

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4558 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Contains data for casing sizes 8 5/8 and 5 1/2.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill hole with chat to 4475' and dump 5 sacks cement.
Set 15' rock bridge from 290' to 275' and dump 25 sacks cement.
Mud hole to 40', rock bridge to 30' and dump 10 sacks cement.

STATE CORPORATION COMMISSION
JAN 26 1966
1-26-66
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering & Construction Company
Address Box 950, El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Laura Bawdle
El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 25th day of January, 19 66

commission expires 9-27-67

Ronald P. Hanson
Notary Public.


COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company: PICKRELL DRILLING CO.
Farm: Alexander No. 1

SEC. 3 T. 30 R. 14W
NW NW NW

Total Depth. 4558'
Comm. 12-22-58 Comp. 1-15-59
Shot or Treated.
Contractor.
Issued. 2-6-60



Elevation. 1975 RB

Production. Dry

8 5/8" CASINO: 360' cem/225 sx.
5 1/2" 4456.5' cem/100 sx.

Figures indicate Bottom of Formations.

clay & sand	190
Red Rock	358
Red Rock & shale	854
Gyp	920
Anhy..	980
Blue shale	1044
Red Bed & salt	1640
shale & shells	1714
shale.	1940
lime	1965
lime & shale	2075
lime.	2435
lime & shale.	2605
shale	2710
lime & shale	3175
lime	3260
lime & shale	3635
lime	3875
lime	4549
Simoson	4552
lime	4558 — T.D.
Total Depth	

TOPS:

Heebner	3838
Toronto	3849
Douglas	3877
Brown Lime	3995
Lansing	4010
Base Kansas City	4385
Conglomerate	4483
Viola	4501 — Top of Perf.
Simpson shale	4536
Simpson dolomite	4542
Simpson sand	4546

Perf.

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1966
1-26-66
CONSERVATION DIVISION
Wichita, Kansas