

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-13181-00-00
Spot: NWNESW Sec/Twnshp/Rge: 1-20S-15W
2310 feet from S Section Line, 1650 feet from W Section Line
Lease Name: DUNAVAN Well #: 1
County: BARTON Total Vertical Depth: 3608 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3600		110 SX
SURF	8.625	250		200 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/11/2013 12:00 AM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F G HOLL Phone: (620) 793-0915

Proposed Plugging Method: Ordered 320 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/11/2013 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 875' and 175'.
Ran tubing to 3500' and pumped 10 sx gel followed w/50 sx cement and 100 # hulls. Pulled tubing to 1350' and pumped 40 sx cement w/100 # hulls. Pulled tubing to 875' and pumped 40 sx cement. Pulled tubing to 400'. Circulated cement to surface w/100 sx cement. Cement coming out around surface pipe. Lost circulation at casing. Pulled tubing to 60' and pumped 20 sx cement. Circulation of cement at casing. Pulled braden head and casing off with unit rusted out below ground level. Topped off w/20 sx cement. Will check later.

GPS: 38.33983 -098.93443

Perfs:

Top	Bot	Thru	Comments
3598	3608		

Remarks: ALLIED OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
01/30/14 (TECHNICIAN)

KCC WICHITA

CM

DEC 27 2013

JAN 28 2014

RECEIVED

Form CP-2/3