

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21030-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 13-24S-17W
1652 feet from N Section Line, 341 feet from W Section Line
Lease Name: HAWLEY Well #: 5-13
County: EDWARDS Total Vertical Depth: 4425 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4250 | | WITH 2 SX CMT |
| CIBP | | 4391 | | |
| PROD | 4.5 | 4418 | 0 | WITH 250 SX CMT |
| SURF | 8.625 | 264 | | WITH 210 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2014 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ADAM APLEY Company: F.G. HOLL COMPANY Phone: (316) 684-8481

Proposed Plugging Method: SET CIBP @ 4250' WITH 2 SX CMT. PERFORATE 4 1/2" @ 1125'. PUMP CMT DOWN 4 1/2" & CIRCULATE UP THE 8 5/8".

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/09/2014 12:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4250' WITH 2 SX CMT ON TOP WITH DUMP BAILER. PRESSURED TESTED 4 1/2" TO 400 PSIG. PERFORATED 4 1/2" @ 1125'. PUMPED 10 SX GEL FOLLOWED BY 310 SX CMT. HAD GOOD CIRCULATION BUT THE BRADEN HEAD PLUGGED OFF & PRESSURE ROSE TO 600 PSIG. PUMPED 90 SX CMT DOWN THE 8 5/8" X 4 1/2" ANNULUS. MAXIMUM PRESSURE 500 PSIG. INITIAL SHUT IN PRESSURE 400 PSIG.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4303 | 4331 | | |

KCC WICHITA
JAN 14 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
JAN 10 2014
KCC DODGE CITY

Signed: Richard M. Lacey
01/30/14 (TECHNICIAN)