

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-01673-00-01
Spot: NWSENE Sec/Twnshp/Rge: 28-11S-19W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: BERLANDE OWWO Well #: 1-3
County: ELLIS Total Vertical Depth: 3504 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3004		
PROD	4.5	3504		125 SX
SURF	8.625	260		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/07/2014 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL CO. Phone: (785) 623-1580

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
CIBP at 3004'
Squeeze at 1160' w/200 and 50 sx cement
Squeeze at 620' w/350 sx cement
Perforations-2976' - 2989'
Bad casing

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/07/2014 2:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech Wireline Service perforated at 260', 350' and 1900'. Express Well Service ran in hole with tubing to 2909'. Allied rigged to tubing and mixed and pumped 100 sx cement w/250 # hulls mixed in. Pulled tubing to 1813'. Allied rigged to tubing and mixed and pumped 100 sx cement w/250 # hulls mixed in to circulate cement up 4 1/2" casing. Pulled tubing. Rigged to 4 1/2" casing and pumped 15 sx cement to pressure w/200 psi and 200 psi shut in pressure. Rigged to 8 5/8" casing and pumped into instant pressure.

GPS: 39.06989 -099.42998
3808' FSL 1008' FEL NW NW SE NE

Perfs:

Top	Bot	Thru	Comments
2976	2989		

KCC WICHITA

Remarks: ALLIED CEMENTING CO TICKET # 55005

JAN 14 2014

Plugged through: TBG

RECEIVED

District: 04

Signed _____ (TECHNICIAN)

[Handwritten Signature]
01/30/14

CM

JAN 08 2014