

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-121-02475-00-00
Spot: SESWSWNW Sec/Twnshp/Rge: 5-17S-22E
2856 feet from S Section Line, 4799 feet from E Section Line
Lease Name: BEETS Well #: 1-P
County: MIAMI Total Vertical Depth: 650 feet

Operator License No.: 34483

Op Name: L & P ENTERPRISES, LLC

Address: 29975 INDIANAPOLIS RD
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	650		10 SX
SURF	10	50		10 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/19/2013 3:00 PM

Plug Co. License No.: 34483

Plug Co. Name: L & P ENTERPRISES, LLC

Proposal Rcvd. from: KEVIN WISEMAN

Company: L & P ENTERPRISES, LLC

Phone: (913) 238-0404

Proposed Spot 10 sacks of cement on top of packer, cement from 300' to surface. Cement 2" complete.
Plugging
Method:

Plugging Proposal Received By: TAYLOR HERMAN

WitnessType: NONE

Date/Time Plugging Completed: 08/23/2013 3:00 PM

KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

WASHED 1" PIPE DOWN TO BOTTOM INSIDE THE 2" AND PUMPED CEMENT TO THE SURFACE. WASHED 1" PIPE DOWN TO 650' ON THE BACKSIDE OF THE 2" AND PUMPED 10 SACKS OF CEMENT. PULLED THE 1" PIPE UP TO 500' AND PUMPED 10 SACKS OF CEMENT. PULLED THE 1" PIPE UP TO 300' AND PUMPED CEMENT TO THE SURFACE.

RECEIVED

JAN 09 2014

KCC Chanute Dist. #3

TH

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 13 2014

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman
8/30/14 (TECHNICIAN)