

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21194-00-00
Spot: S2S2NW Sec/Twnshp/Rge: 10-32S-18W
2299 feet from N Section Line, 1334 feet from W Section Line
Lease Name: HILT Well #: 1
County: COMANCHE Total Vertical Depth: 5750 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4930		WITH 2 SX CMT
COND	20	74		
PROD	5.5	5282	2520	WITH 250 SX CMT
SURF	8.625	708		WITH 325 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/31/2013 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 5028' OR SAND TO 4930' WITH 5 SX CMT. PLUG AT 1090' WITH 15 SX GEL & 50 SX CMT. PLUG AT 730' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/31/2013 12:30 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

CIBP @ 4930' WITH 2 SX CMT. 1ST PLUG AT 1090' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 730' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5208	5218		
5124	5132		
4980	4986		

Remarks: USED 60/40 POZMIX 1/4# FLO SEAL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

RECEIVED

JAN - 8 2014

KCC DODGE CITY

Signed

Nathan Willis
5/01/30/14

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 13 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3