

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20883-00-01
Spot: SWNESESE Sec/Twnshp/Rge: 25-30S-41W
705 feet from S Section Line, 356 feet from E Section Line
Lease Name: HOFFMAN-JOHNS WF 'B' (PIC Well # 1-25)
County: STANTON Total Vertical Depth: 5700 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5400		WITH 2 SX CMT
DVT		2505		WITH 225 SX CMT
PROD	5.5	5605	0	WITH 375 SX CMT
SURF	8.625	1618		WITH 700 SX CMT

Well Type: EOR UIC Docket No: E30047.2 Date/Time to Plug: 12/16/2013 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SCOTT HAMPEL Company: MCCOY PETROLEUM Phone: (316) 636-2737

Proposed Plugging Method: SET CIBP @ 5370' WITH 2 SX CMT. PLUG AT 1650' WITH 25 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2013 1:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5400' WITH 2 SX CMT. 1ST PLUG AT 1659' WITH 30 SX CMT. 2ND PLUG PERFORATE @ 600' & PUMPED 150 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5418	5428		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

DEC 30 2013

KCC DODGE CITY

Signed

[Signature]
cc to MIC of 12/14
01/30/14
(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

JAN 13 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3