

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21408-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 17-33S-24W
2237 feet from N Section Line, 2306 feet from E Section Line
Lease Name: MCGONIGLE Well #: 1
County: CLARK Total Vertical Depth: 5965 feet

Operator License No.: 5254
Op Name: MIDCO EXPLORATION, INC.
Address: PO BOX 1278
WESTMONT, JL 60559

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5350		WITH 2 SX CMT
COND	20	62		
PROD	4.5	5757	4030	WITH 300 SX CMT
SURF	8.625	800		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/02/2014 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 5350' WITH 2 SX CMT. PLUG AT 1020' WITH 40 SX CMT. PLUG AT 830' WITH 50 SX CMT. PLUG AT 540' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/02/2014 3:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

CIBP @ 5350' WITH 2 SX CMT. LOADED HOLE WITH 50 BBL MUD. 1ST PLUG AT 1020' WITH 40 SX CMT. 2ND PLUG AT 830' WITH 50 SX CMT. 3RD PLUG AT 540' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. GOOD RETURNS DURING PUMPING.

Perfs:

Top	Bot	Thru	Comments
5384	5388		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed Nathan Willis (TECHNICIAN)

RECEIVED

JAN - 8 2014

KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 13 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3