

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21144-00-01
Spot: SWNE Sec/Twnshp/Rge: 18-33S-24W
1946 feet from N Section Line, 1091 feet from E Section Line
Lease Name: SHAFFER TRUST OWWO Well #: 1-18
County: CLARK Total Vertical Depth: 7253 feet

Operator License No.: 5254
Op Name: MIDCO EXPLORATION, INC.
Address: PO BOX 1278
WESTMONT, IL 60559

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5580		WITH 2 SX CMT
CIBP		6700		WITH 2 SX CMT
PROD	5.5	7250	4200	WITH 385 SX CMT
SURF	8.625	829		WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/30/2013 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 50' ABOVE PERFS WITH 2 SX CMT. LOAD HOLE WITH MUD. PLUG AT 1020' WITH 40 SX CMT. PLUG AT 860' WITH 50 SX CMT. PLUG AT 540' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2013 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP'S @ 6700' & 5580' WITH 2 SX CMT EACH. LOADED HOLE WITH MUD. 1ST PLUG AT 1020' WITH 40 SX CMT. 2ND PLUG AT 860' WITH 50 SX CMT. 3RD PLUG AT 540' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed

Eric MacLaren
01/30/14

(TECHNICIAN)

KCC WICHITA

RECEIVED

JAN 10 2014

KCC DODGE CITY

JAN 16 2014

RECEIVED

Form CP-2/3

any