

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20339-00-00
Spot: NENESWSE Sec/Twnshp/Rge: 18-20S-39W
1304 feet from S Section Line, 1357 feet from E Section Line
Lease Name: FOSTER Well #: 1
County: GREELEY Total Vertical Depth: 2930 feet

Operator License No.: 7271
Op Name: BARTLING OIL COMPANY
Address: 1001 CANYON EDGE DR
AUSTIN, TX 78733

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2928	0	WITH 550 SX CMT
SURF	8.625	290		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/14/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GUS OCHSNER Company: BARTLING OIL Phone: (620) 376-2249

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/14/2014 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG STUCK. FREE POINT @ 1550'. SHOT TBG OFF @ 1500'. SPOT 50 SX CMT W/3% CC & 100# HULLS AT 1498' THROUGH TBG. TOOH WITH TBG. WAIT 2 HOURS & TAG TOC @ 1410'. RUN TBG TO 1200'. BREAK CIRCULATION WITH WATER. FULL RETURNS. CIRCULATE CMT TO SURFACE WITH 100 SX CMT & 100# HULLS. TOOH WITH TBG. TOP OFF 4 1/2" WITH 15 SX CMT. STAYED FULL. PUMP 10 SX CMT DOWN THE ANNULUS TO 450#.

Perfs:


Top	Bot	Thru	Comments
2884	2897		
2845	2856		
2806	2822		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS A COMMON CEMENT BY CONSOLDIATED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

JAN 23 2014

KCC DODGE CITY

KCC WICHITA

Form CP-2/3

JAN 27 2014

RECEIVED

ROM