

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21474-00-00  
Spot: NWSESWSW Sec/Twnshp/Rge: 2-20S-19W  
658 feet from S Section Line, 662 feet from W Section Line  
Lease Name: BRADFORD Well #: 1-2  
County: PAWNEE Total Vertical Depth: 2425 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2210		WITH 2 SX CMT
PLG	4.5	2350		
PROD	4.5	2405	0	WITH 125 SX CMT
SURF	8.625	547		WITH 600 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/07/2013 9:30 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: CIBP @ 2210' & 2 SX CMT. PERFORATE AT 1400' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: DANIEL SELLERS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/07/2014 4:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 2210' WITH 2 SX CMT ON TOP WITH DUMP BAILER. PERFORATED 4 1/2" @ 1250'. PUMPED DOWN THE 4 1/2" WITH 100 SX CMT & LOST CIRCULATION. DISPLACED CMT TO 600'. PERFORATED 4 1/2" @ 580'. PUMPED 150 SX CMT DOWN THE 4 1/2" CIRCULATING CMT TO SURFACE UP THE 8 5/8" X 4 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2260	2292		

KCC WICHITA  
JAN 14 2014  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED 10 SI FOR 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

RECEIVED  
JAN 10 2014

Signed Richard M. Lacey (TECHNICIAN)  
01/28/14

KCC DODGE CITY