

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21269-00-00
Spot: N2NWSW Sec/Twnshp/Rge: 10-20S-19W
2324 feet from S Section Line, 4610 feet from E Section Line
Lease Name: HARMS Well #: 10-12
County: PAWNEE Total Vertical Depth: 4300 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2536	0	WITH 100 SX CMT
SURF	8.625	456		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/02/2014 11:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: CASING PARTED @ 780'. WILL TRY TO SPOT PLUGS @ 2230' & 1340' IF THEY CAN GET TBG DOWN THAT FAR. PULL TBG TO 800' & CIRCULATE CMT UP 4 1/2" & 8 5/8" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/02/2014 2:50 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CASING PARTED @ 780'. UNABLE TO GET ANY DEEPER THAN 814'. PUMPED 125 SX CMT DOWN TBG AT 814' TO CIRCULATE CMT UP THE CASING. PUMPED ANOTHER 115 SX CMT TO CIRCULATE CMT UP 4 1/2" X 8 5/8" ANNULUS. PULLED TBG & TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2396	2410		
2334	2361		
2288	2312		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 13 2014
CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Eric MacLaren
01/28/14 (TECHNICIAN)

RECEIVED
JAN - 6 2014
KCC DODGE CITY