

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-03110-00-00
Spot: SENENE Sec/Twnshp/Rge: 30-28S-2E
4347 feet from S Section Line, 282 feet from E Section Line
Lease Name: SCOTT Well #: 1
County: SEDGWICK Total Vertical Depth: 2247 feet

Operator License No.: 32032
Op Name: BEECHCRAFT CORPORATION
Address: 10511 E. CENTRAL BO15-A02
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|---------|------------|-------------|----------|
| COND | 16 | 100 | | |
| | 11 12.5 | 775 | | |
| | 12 10 | 1915 | | |
| PROD | 5.5 | 2208 | | 0 SX |
| PROD | 8 | 2225 | | |
| SURF | 8.625 | 2233 | | 0 SX |

Well Type: GSO UIC Docket No: _____ Date/Time to Plug: 12/16/2013 8:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: DAN MUERTA Company: T&C MANUFACTURING Phone: (620) 793-5483

Proposed Plugging Method: AS PER KCC RULES & REGULATIONS

Plugging Proposal Received By: BRANDON MILNER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2013 12:00 PM KCC Agent: BRANDON MILNER

Actual Plugging Report:

12/13/13 RIGGED UP ON SCOTT #1. RAN 40 BBLs OF BRINE WATER TO KILL WELL. RAN MIT ON ANNULAR SPACE WITH 30 MINUTE TEST. PRESSURE RAN FROM 329-400 PSI FROM DIFFERING WATER TEMPERATURES. INSTALLED TIW VALVE OVER 2 3/8" TUBING AND INSTALLED BOP TO WELLHEAD. RELEASED LOC-SET PACKER AT 2,180'. PULLED TUBING OUT OF HOLE (70 JOINTS). WITH WIRELINE TRUCK RAN 5 1/2" GAUGE RING TO 2200'. RAN IN AND SET CEMENT RETAINER AT 2195'. 12/17/13 RAN 2 3/8" TUBING DOWN THROUGH CEMENT RETAINER AND SPOTTED 20 SX OF CEMENT IN OPEN HOLE. PULLED TUBING OUT OF RETAINER AND SPOTTED 10 SX OF CEMENT ON TOP TO APPROXIMATELY 2105'. SPOTTED 7 SX OF GEL AT 2105'. PULLED TUBING TO 1508' AND SPOTTED 15 SX OF CEMENT TO 1350'. SPOTTED 10 SX OF GEL AT 1350'. PULLED TUBING TO 250' AND SPOTTED 40 SX OF CEMENT TO SURFACE INSIDE OF 5 1/2" CASING. 12/19/17 CUT OFF WELLHEAD AT 5 FEET BELOW SURFACE AND VISUALLY SAW CEMENT WAS TO SURFACE ON ALL CASING. WELDED METAL CAP ON WELLHEAD.

Perfs:

Remarks: TICKET #09682

Plugged through: TBG

KCC WICHITA
JAN 14 2014
RECEIVED

District: 02

Signed Brandon Milner
01/28/14 (TECHNICIAN)