

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21807-00-00
Spot: NENESE Sec/Twnshp/Rge: 20-15S-23W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: SNODGRASS Well #: 1
County: TREGO Total Vertical Depth: 4315 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4304		150 SX
SURF	8.625	285		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/15/2014 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: KYLE RANDA Company: FRITZLER TRUCKING Phone: (785) 798-3306

Proposed	Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Plugging	Perforations: 4304' - 4315'.
Method:	Tubing and rods stuck in hole at 2085'. Can not get out. Tied on to casing and tried to pump into plug. Pumped up to 1000 psi and will not take fluid. Hole is bridged off at 2085'. DV Tool set at 1765' w/425 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/15/2014 12:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2084' and pumped 201 sx cement w/300 # hulls. Good circulation of cement.
Pulled tubing. Topped off w/14 sx cement. Tied on to backside and squeezed w/15 sx cement.
150 psi shut in pressure.
GPS: 38.73194 -099.89578

Perfs:

Top	Bot	Thru	Comments
4304	4315		

Remarks: CONSOLIDATED CEMENTING TICKET # 43060

Plugged through: TBG

District: 04

Signed *Marvin Mills*
01/30/14 (TECHNICIAN) CM

KCC WICHITA

JAN 17 2014

JAN 28 2014

RECEIVED