

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22482-00-00

Spot: SWSNWNW

Sec/Twnshp/Rge: 1-18S-29W

1170 feet from N Section Line,

790 feet from W Section Line

Lease Name: PECK 1

Well #: 1

County: LANE

Total Vertical Depth: 4625 feet

Operator License No.: 34158

Op Name: O'BRIEN RESOURCES, LLC

Address: PO BOX 6149

SHREVEPORT, LA 71136

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

SURF	8.625	272		WITH 200 SX CMT
------	-------	-----	--	-----------------

Well Type: DH

UIC Docket No:

Date/Time to Plug: 01/15/2014 9:00 AM

Plug Co. License No.: 34233

Plug Co. Name: MAVERICK DRILLING LLC

Proposal Rcvd. from: JEREMY STUCKY

Company: MAVERICK DRILLING LLC

Phone: (316) 262-6700

Proposed Plugging Method: 1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1290' WITH 80 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN

WitnessType: NONE

Date/Time Plugging Completed: 01/15/2014 11:00 PM

KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1290' WITH 80 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed

(TECHNICIAN)

RECEIVED

JAN 23 2014

KCC DODGE CITY

KCC WICHITA

JAN 27 2014

RECEIVED

Form CP-2/3