

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-01047-00-01
Spot: SWNENE Sec/Twnshp/Rge: 19-13S-20W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: LANG Well #: 4
County: ELLIS Total Vertical Depth: 3915 feet

Operator License No.: 30762
Op Name: OIL COMPANY OF AMERICA, INC.
Address: 1200 MAIN STE 310
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3906		150 SX
SURF	8.625	190		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/17/2014 10:30 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: ROGER MOSES Company: ULTIMATE WELL SERVICE, LLC Phone: (785) 656-1729

Proposed	Ordered 750 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Plugging	Tubing stuck in hole at 1860'.
Method:	DV Tool at 1585' w/450 sx cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/17/2014 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 1859' and pumped 440 sx cement w/500 # hulls. Ran out of cement and sent for more. Pulled tubing out. Waited on cement. Ran tubing back in to 1000' and pumped 20 sx cement. Good circulation of cement. Pulled tubing out and topped off w/10 sx cement. Hole standing full. Back side full of cement.

GPS: 38.91120 -099.58023

Remarks: ALLIED CEMENT TICKET # 55013

Plugged through: TBG

District: 04

Signed *Marvin Mills*
01/20/14 (TECHNICIAN) CM

JAN 22 2014

KCC WICHITA

Form CP-2/3

JAN 28 2014

RECEIVED