

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-25306-00-00  
Spot: SESENWNW Sec/Twnshp/Rge: 28-16S-25W  
1086 feet from N Section Line, 1318 feet from W Section Line  
Lease Name: WHITE STAR STUD RANCH Well #: 1  
County: NESS Total Vertical Depth: 4635 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	1918		CEMENTED WITH 175 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	5.5	4634	0	WITH 170 SX CMT
SURF	8.625	264		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/02/2014 9:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Revd. from: GLENN DINKEL Company: PALOMINO PETROLEUM Phone: (785) 735-8199

Proposed Plugging Method: RAN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 1920' & CIRCULATED CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/02/2014 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4358' & PUMPED 35 SX CMT & 150# HULLS. PULL TBG TO 1918' & PUMP 210 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4529	4534		
4524	4527		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

**KCC WICHITA**

**JAN 16 2014**

**RECEIVED**

District: 01

**RECEIVED**

**JAN 13 2014**

**KCC DODGE CITY**

Signed

*Michael Maier*  
01/30/14

(TECHNICIAN)

*RM*