

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20010-00-00
Spot: SE Sec/Twnshp/Rge: 5-26S-39W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: AKERS BARNEY Well #: 1-5
County: HAMILTON Total Vertical Depth: 2750 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O CONNOR BLVD., SUITE 200
IRVING, TX 75039

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 7 | 2749 | 0 | WITH 185 SX CMT |
| SURF | 10.75 | 744 | | WITH 500 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/20/2014 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: ALAN Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 01/21/2014 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TAG FILL UP IN 7" CASING @ 2462'. PERFS ARE COVERED. SPOT 20 SX CMT AT 2462'. PERFORATE @ 1975'. RUN TBG TO 1975' & SPOT 60 SX CMT. TOOH W/TBG. LOAD CASING & SQUEEZE 5 BBL CMT INTO PERFS. CUT CASING AT 797'. ATTEMPT TO PULL. COULD NOT. 1/21/13: RAN PACKER ON TBG TO 93'. BREAK CIRCULATION. HAD FULL CIRCULATION THROUGH CUT IN 7" CASING OUT 7" X 10 3/4" ANNULUS. CIRCULATE CMT TO SURFACE WITH 330 SX CMT LEAVING THE 7" CASING & 7" X 10 3/4" ANNULUS FULL OF CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2615 | 2668 | | |
| 2571 | 2573 | | |
| 2545 | 2547 | | |
| 2512 | 2524 | | |

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
JAN 23 2014
KCC DODGE CITY

Signed

Ken Jehlik
01/30/14
(TECHNICIAN)

KCC WICHITA

JAN 27 2014

RECEIVED

Form CP-2/3