

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-00150-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 19-29S-34W
2545 feet from S Section Line, 2460 feet from E Section Line
Lease Name: PONCETI F E Well #: 1-19
County: HASKELL Total Vertical Depth: 2732 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA,
Address: 5205 N. O CONNOR BLVD., SUITE 200
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2535	0	WITH 125 SX CMT
SURF	10.75	641		WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/15/2014 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PERFORATE @ 1370' WITH 75 SX CMT. PERFORATE @ 800' WITH 50 SX CMT. PERFORATE @ 675' & CIRCULATE CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL
Date/Time Plugging Completed: 01/16/2014 3:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TOP OF FISH @ 1394' PERFORATE @ 1388' & SQUEEZE WITH 75 SX CMT. TAGGED AT 1095'. PERFORATE @ 800' & SQUEEZE WITH 50 SX CMT. TAGGED AT 733'. PERFORATE @ 650' & SQUEEZE WITH 300 SX CMT. CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2712	2718		
2659	2700		
2593	2602		
2551	2574		
2536	2546		

KCC WICHITA
JAN 24 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED
JAN 21 2014
KCC DODGE CITY