

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20431-00-00
Spot: NWNWNWNW Sec/Twnshp/Rge: 28-27S-27W
230 feet from N Section Line, 190 feet from W Section Line
Lease Name: ETLING SWD Well #: 28-1
County: GRAY Total Vertical Depth: 6800 feet

Operator License No.: 34320
Op Name: LASSO ENERGY LLC
Address: PO BOX 465
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4850		WITH 2 SX CMT
CIBP		5078		
CIBP		5507		
CIBP		5640		
CIBP		5825		
CIBP		5995		
PROD 7		6056	1580	WITH 375 SX CMT
SURF 9.625		1515		WITH 600 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2013 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4850' WITH 2 SX CMT. PLUG AT 1540' WITH 25 SX GEL & 75 SX CMT. PLUG AT 760' WITH 60 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 12/30/2013 6:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

CIBP @ 4850' WITH 2 SX CMT. LOADED HOLE WITH 25 SX GEL. 1ST PLUG AT 1560' WITH 75 SX CMT. 2ND PLUG AT 760' WITH 60 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5846	5849		
5808	5810		
5688	5700		
5536	5542		
5228	5236		
5069	5071		
5056	5062		
4892	4902		

Remarks: USED 60/40 POZMIX 1/4# FLO SEAL BY COPELAND ACID & CEMENT.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 13 2014
CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED
JAN - 8 2014
Signed Wethel Willis
01/30/14
(TECHNICIAN)
KCC DODGE CITY