

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-22160-00-00  
Spot: W2SESENE Sec/Twnshp/Rge: 12-26S-12W  
2906 feet from S Section Line, 344 feet from E Section Line  
Lease Name: LENNI Well #: 1  
County: PRATT Total Vertical Depth: 4350 feet

Operator License No.: 34320  
Op Name: LASSO ENERGY LLC  
Address: PO BOX 465  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3950		WITH 2 SX CMT
DVT	4.5	2000		WITH 245 SX CMT
PROD	4.5	4345	900	WITH 415 SX CMT
SURF	10.75	278		WITH 235 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/14/2014 11:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 3950' & 2 SX CMT. PLUG AT 700' WITH 10 SX GEL & 40 SX CMT. PLUG AT 300' WITH 70 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/14/2014 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3950' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 700' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 300' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4141	4145		
4002	4145		
3995	4002		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

RECEIVED  
JAN 16 2014  
KCC DODGE CITY

Signed Stephen J. Pfeifer  
(TECHNICIAN)

KCC WICHITA

JAN 21 2014

RECEIVED

Form CP-2/3