

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21924-00-02
Spot: NWSWNE Sec/Twnshp/Rge: 19-31S-13W
3525 feet from S Section Line, 2206 feet from E Section Line
Lease Name: DEWITT A Well #: 1-19
County: BARBER Total Vertical Depth: 4345 feet

Operator License No.: 31938
Op Name: INDIAN OIL CO., INC.
Address: PO BOX 209 2507 SE US 160 HWY
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3200		WITH 2 SX CMT
CIBP		3645		WITH 2 SX CMT
PROD	4.5	3808	2104	WITH 175 SX CMT
SURF	10.75	249		WITH 200 SX CMT

Well Type: SWD UIC Docket No: _____ Date/Time to Plug: 01/10/2014 1:30 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP'S @ 3645 WITH 2 SX CMT & 3200' WITH 2 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 280' WITH 75 SX CMT. PLUG AT 60' WITH 35 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/10/2014 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP'S @ 3645' & 3200'. PUT 2 SX CMT ON TOP OF EACH CIBP THROUGH DUMP BAILER. 1ST PLUG AT 619' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 293' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3696	3700		
3246	3250		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

JAN 16 2014

KCC DODGE CITY

Signed

Steve Pfeifer
cc to me 01/21/14
01/30/14

TECHNICIAN)

KCC WICHITA

JAN 21 2014

RECEIVED