

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20094-00-00
Spot: SENWSWNE Sec/Twnshp/Rge: 6-35S-34W
3324 feet from S Section Line, 1995 feet from E Section Line
Lease Name: DOWDY Well #: 1-6
County: SEWARD Total Vertical Depth: 6673 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 W 112TH
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6150		WITH 2 SX CMT
PROD	5.5	6671	1991	WITH 175 SX CMT
SURF	8.625	1423		WITH 750 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/03/2013 5:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 6440' WITH 2 SX CMT. PLUG AT 1450' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 01/03/2014 9:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 6150' WITH 2 SX CMT. 1ST PLUG AT 1449' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 619' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 21 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6626	6636		
6491	6495		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Eric MacLaren

RECEIVED

JAN - 8 2014

KCC DODGE CITY

RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

JAN 13 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3