

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22759-00-00
Spot: NWSWNWNE Sec/Twnshp/Rge: 2-18S-8W
907 feet from N Section Line, 2537 feet from E Section Line
Lease Name: GUSTUS UNIT "A" Well #: 1-2
County: RICE Total Vertical Depth: 3350 feet

Operator License No.: 34579
Op Name: COBALT ENERGY LLC
Address: 115 S. BELMONT #12 PO BOX 8037
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	380		180 SXS CLASS A CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/17/2013 5:00 PM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: WES PFAFF Company: SOUTHWIND DRILLING INC Phone: (620) 566-7094

Proposed
Plugging
Method:

PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: NONE
Date/Time Plugging Completed: 12/18/2013 1:00 AM KCC Agent: DAN FOX

Actual Plugging Report:

Perfs:

ON 12/17/2013 SOUTHWIND DRILLING INC SPOT 35 SX PLUG @ 3348' ON TOP OF THE ARBUCKLE. THEN 35 SX SPOT PLUG @ 1175' FOR BOTTOM SALT PLUG THEN 35 SX @ 775' FOR TOP SALT PLUG THEN 35 SX @ 434 FOR 50' BELOW SURFACE CASING. THEN SPOT 20 SX PLUG @ 60' AND CIRCULATED TO SURFACE, WITH A 60/40 POS MIX & 4% GEL. 20 SX IN THE RAT HOLE NO MOUSE HOLE WAS DRILLED. QUALITY WELL SERVICE WAS CEMENT CO. OUT OF RUSSELL KS, WITH 180 SX TOTAL. TICKET #7625.

Remarks: DRY HOLE

Plugged through: DP

KCC WICHITA

JAN 14 2014

RECEIVED

District: 02

Signed

Daniel J. Fox
01/30/14
(TECHNICIAN)