

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20630-00-00
Spot: N2S2NE Sec/Twnshp/Rge: 27-29S-39W
3599 feet from S Section Line, 1313 feet from E Section Line
Lease Name: GOERTZEN Well #: 1-27
County: STANTON Total Vertical Depth: 5825 feet

Operator License No.: 30425
Op Name: DNR OIL AND GAS, INC.
Address: 12741 E CALEY UNIT 142
CENTENNIAL, CO 80111

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5724		
DVT		3174		CIRCULATED TO SURFACE
PROD	4.5	5818	0	WITH 200 SX CMT
SURF	8.625	1735		WITH 750 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2014 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MARC VENJOHN Company: DNR OIL & GAS Phone: (303) 825-8956

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. LOAD HOLE WITH MUD. PLUG AT 1770' WITH 30 SX CMT. CIRCULATE CMT TO SURFACE FROM 550'. TOP OOF & PRESSURE ANNULUS.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/21/2014 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

PUMP 25 SX CMT WITH 100# HULLS AT 5670'. PULL TO 1777' & LOAD HOLE WITH MUD. PLUG AT 1777' WITH 30 SX CMT. FULL CIRCULATION. PUMP 35 SX CMT FROM 550' TO 0'. TOOH WITH TBG. TOP OFF WITH 2 SX CMT. PUMP 3 SX CMT DOWN THE ANNULUS TO 350#.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

JAN 23 2014

KCC DODGE CITY

Signed

01/30/14

(TECHNICIAN)

KCC WICHITA Form CP-2/3

JAN 27 2014

RECEIVED

1922