

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21456-00-01
Spot: NWSEWNE Sec/Twnshp/Rge: 12-28S-13W
989 feet from N Section Line, 1686 feet from E Section Line
Lease Name: NEWLIN Well #: 1-12
County: PRATT Total Vertical Depth: 4380 feet

Operator License No.: 32166
Op Name: DUNNE EQUITIES OPERATING, INC.
Address: 8100 E. 22ND ST. NO #1100
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4180		WITH 2 SX CMT
COND	10.75	327		WITH 325 SX CMT
PROD	5.5	4380	2530	WITH 125 SX CMT
SURF	8.625	1103		WITH 225 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/09/2014 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 4180' WITH 2 SX CMT. PLUG AT 1160' WITH 15 SX GEL & 50 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. CHECK 10 3/4" X 8 5/8" ANNULUS WITH 50 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: NONE
Date/Time Plugging Completed: 01/09/2014 3:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

CIBP @ 4180' WITH 2 SX CMT. LOADED HOLE WITH MUD. 1ST PLUG AT 1160' WITH 50 SX CMT. 2ND PLUG AT 640' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. 10 3/4" X 8 5/8" ANNULUS WAS VISUALLY CHECKED & FULL OF CMT BY KIRBY LILLARD.

Perfs:

Top	Bot	Thru	Comments
4230	4254		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed

[Handwritten Signature]
01/30/14
(TECHNICIAN)

RECEIVED

JAN 10 2014

KCC DODGE CITY

KCC WICHITA

JAN 16 2014

RECEIVED

Form CP-2/3

[Handwritten Initials]