

15-007-0695-0000

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

DEC 26 1962
12-26-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dec. 16, 1962.

Dear Sir:

Mr. Bob Sargent of Sargants Caseing Pulling has this Service.
date requested permission to plug the following described well:

Mr. Bob Sargent guarantees payment of the plugging fee.

Operator's full Name: W. M. Gruenerwald.

Complete Address: 35 East Wacker Drive Chicago, Illinois.

Lease Name: Allexzander #1 Well No. #1

Location: NW-NE Sec. 29 Twp. 34S Rge. 14 (E) (W) X

County Barber County Total Depth 4743' Oil Well

Abandoned
Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Bob Sargent was instructed to plug the well as follows:

4742' of 5 1/2" oil string. Top perforation at 4670'. Hole
filled with sand to 4378' and 25 sacks cement by Globe
Cementing Co. 957' of 8 5/8" surface pipe circulated with
cement. Hole filled to 500' with mud, 10' rock bridge and
20 sacks cement. Hole filled to 40' with mud, 10' rock bridge
and 10 sacks cement to base of cellar. 3992' of 5 1/2" pipe recovered.
Very truly yours,

Herman J. Astor
Conservation Division Agent