

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

New Address
245 North Water
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1976
4-21-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gallaugher of Gabbert & Jones Inc has this

date requested permission to plug the following described well:

Mr. Gallaugher guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co

Complete Address: 700 Sutton Place 209 E Williams Wichita, KS

Lease Name: E.W.B. Ranch A Well No. 1

Location: 1650' FWL & 2310' FSL ^{SW/4} Sec. 33 Twp. 34s Rge. 14 (E)(W) W

County: Barber Total Depth 4984 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Gallaugher was instructed to plug the well as follows:

428 ft 8 5/8 surface cemented with 300 sacks. Pump plug,

35 sacks cement to 375 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 15 sacks cement to surface. 2 sacks cement in

rat hole.

Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,

Conservation Division Agent