

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

JUN 12 1963
 6-12-63
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Crescent Oil & Gas Corporation

Complete Address: Box 412, Tulsa, Oklahoma

Lease Name: Neu Well No. # 1

Location: C NE NW Sec. 34 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4900 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

342' of 10 $\frac{3}{4}$ " surface pipe, cement circulated with 250

sacks. Fill hole with mud to 240', 1st cementing plug,

$\frac{1}{4}$ sack hulls, cement with 25 sacks. Fill hole with mud

to 40', 2nd cementing plug, $\frac{1}{4}$ sack hulls, cement with

15 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Audie E. Elving
 Conservation Division Agent