

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

FEB 25 1963

2-25-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Lewis Carpenter of Davon Drilling Co. has this

date requested permission to plug the following described well:

Mr. Carpenter guarantees payment of the plugging fee.

Operator's full Name: Publishers Petroleum

Complete Address: 1713 1st National Bank Bldg., Oklahoma City, Okla.

Lease Name: Baier Unit Well No. # 1

Location: NE NW SW Sec. 36 Twp. 34S Rge. 14 (E) (W) W

County Barber Total Depth 4900 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Carpenter was instructed to plug the well as follows:

314' of 8 5/8" surface pipe, cement circulated with 250  
sacks. Fill hole with heavy mud to 180', 1/2 sack of hulls,  
1st cementing plug, cement with 20 sacks. Fill hole to 40'  
with mud, 1/2 sack of hulls. 2nd cementing plug, cement  
with 10 sacks to base cellar. Bridge and cement at hole  
with 2 sacks.

Very truly yours,

Audie Elving  
 Conservation Division Agent