

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 21 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bob Burris of Garvey Drilling Co. has this

date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Trummel Well No. # 1

Location: W/2 W/2 NW Sec. 8 Twp. 31 Rge. 16 (E) (W) W

County Comanche Total Depth 5015 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

502' of 8 5/8" surface pipe, cement circulated. Fill hole
with mud to 240', 1st cementing plug, 1/2 sack hulls, cement
with 20 sacks. Fill hole with mud to 40', 2nd cementing
plug, 1/2 sack hulls, cement with 10 sacks to base cellar.
Rat hole & mouse hole bridged and cemented with 4 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent