

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed November 27, 1967.

Dear Sir:

Mr. Merlin Freeman of Garvey Drilling Company has this
date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas 67202

Lease Name: Robbins Unit Well No. # B-1

Location: App. W/2 NE Sec. 24 Twp. 31 Rge. 16 (E)(W) W

County Comanche Total Depth 4911' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Freeman was instructed to plug the well as follows:

511' of 8 5/8" surface pipe, cement circulated with 350 sacks. Fill
hole with drilling to 500', bridge with 1/2 sack of hulls, and cement
with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug,
bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar.
Bridge rat and mouse holes and cement with 4 sacks.

Very truly yours,

Aubie Elving
Conservation Division Agent