

1 030348

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,971-~~0000~~ *R*

SE NW, SEC. 33, T 30 S, R 14 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6327

Lease Name Mills Well # 1-33

Operator: Kan-Ex, Inc.

County Barber 154.38

Name & Address 110 South Main, Suite 800

Well Total Depth 4750 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 451

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 7:00 pm Day: 31 Month: December Year: 19 84

Plugging proposal received from Dennis Petz

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 800' with 50 sx cement

RECEIVED
STATE CORPORATION COMMISSION

2nd plug at 480' with 40 sx cement

JAN 09 1985

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

1-9-85
CONSERVATION DIVISION
Wichita, Kansas

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:00 pm Day: 31 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 800' with 50 sx cement, 2nd plug at 480' with 40 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(if additional description is necessary, use BACK of this form.)

INVOICED

(if not observed, observe this plugging.)

DATE 1-15-85

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 6459